So I had to start a telco

Or .. How I finally got high speed internet access to my house in 2020

Jared Mauch - Washtenaw Fiber Properties LLC @jaredmauch

Background


- In 2002 I moved to a new home on the outskirts of Ann Arbor, MI
- My employer at the time provided me a T1 to the local pop
- 1.5Mb/s in 2002 symmetric at home was still decent
- Development in and around Ann Arbor was putting in new subdivisions nearby
- I expected broadband would reach my new home eventually (Cable, DSL, FTTx)
- But.. nothing came
- About 2+ (3.3km) miles away from existing service area
 - 12291ft (3.7km) to my house


Where do I live?


- West side of Ann Arbor, MI
- No .. Further west


Keep going...


- Ok, can I describe it as farm adjacent?














So .. problem.. Conflict

- No high speed internet
- Move?
 - US generally seller pays commission based on sale price, significant cost to move
 - Home devalued as no high speed available
- WISP (Wireless ISP) to temporary rescue
- What's a geek to do?

I know...


- Start a telco!
- File a tariff https://washftth.com/tariff/
- ...
- Profit?

Lets back up now

- Research
- Planning
- Finances
- Pre-builds
 - 2018 Started to connect WISP customers to fiber
- Customers
- Internet Access
- Construction
- Contractors
- Fiber


Research

- Access, Costs
 - Tried to get existing providers to build
 - Comcast was most approachable and easy to work with wanted \$50k
 - AT&T was unable to offer anything but DSL
- Technology
 - Active Ethernet
 - GPON (UF-OLT, some drawbacks here)
- Marketing!
 - Talked to many people
 - Mailed letters to potential subscribers
- Talked to many ISPs doing existing FTTH
- Community Groups



Planning

- Purchased fusion splicer in 2016
- Purchased first 2km of Fiber in 2017
- Purchased OTDR in 2018
- Design and Permitting
 - Drew up master plans
 - Filed tarriff with regulators
 - Joined MissDIG (811) system
 - Permit filed for April 2019
 - Issued September 2019
- Time of year pushed schedule into 2020



Finances .. or .. start small


- Key was to spread out costs over a longer period of time
- Found distributors for underground supplies
- A little bit here, a little bit there goes a long way
- Planning told me it would be a \$60k project (at least)
- Had to line up money, bonus, HELOC, customer payments
- Pre-pay model copied from VBFiber
 - Can pay \$5,000 up-front and receive \$50 credit for 100 months
 - Stays with property
 - Keeps customer paying something
 - Offset startup costs (£¢\$)

Pre-builds

- Worked with existing WISP who had antennas on my house
- Pre-wired neighbors with fiber at my expense
- Pre-wired and pre-constructed my property
- Racks, Fiber distribution, patch panels...







Supplies and Supply runs!







Customer Acquisition

- Local county has tool MapWashtenaw
- Can look at property shapes
- Get owner names
- Sent them a letter
 - In the mail
 - On paper
 - Yes in 2019
 - Really
- Invited to neighborhood meeting
- Construction start letter also went out to people who did not sign up
 - More people signed up
- Around 70% of homes passed signed up

Internet Access

- ACD.net
 - Had to enable IPv6 for me
- 123.net
 - Connection Pending
- Detroit IX
 - Connection Pending
- ARIN
 - Can apply for IPv6 space
 - Can apply for IPv4 space if you have IPv6
 - Already had an ASN

Contractors


 Have a good working relationship with them

- Perhaps buy them food
 - Keep them happy and working
- Resolve issues along the way
- Consider policies for social media posts
- Get a good referral
- Make sure they have all the right equipment



Expect problems

- Cursed corner!









My Equipment

- Purchased Ditch Witch JT820 Drill
 - Vintage 1995
 - \$8,000
- Borrowed cable plow
 - Used to bury service drops
 - Owned by WISP





Theft of equipment!





Marketplace > Mis

Ditch witch z10 Aurora, IL · over a

\$6,500

2006 Ditch Witch boring attachmen

Condition Brand



Seller Information




Send seller a me







Construction issues



Unbudgeted costs

- Survey and staking of right of way
 - \$5,000
- Marking wire for conduit to end stop-work order
 - \$300
- Employee badges
 - Helpful during COVID-19
- Water
 - \$1,500 (may be revised) for directional drill



Fiber Installation





Build your own tools!

- Built a small fiber blower
- Worked decent
- 2,700 (822m) feet without issue




Splicing time!





OTDR time!

- Ouch!



Some fixes ...

- Better



Scheduled install

- August 27th
- I know what I'm doing, so turn-up should be easy right? RIGHT?
- НАНАНАНАНАНАНАНАНАНАНАНАНАНАНАНАН
- Sorted through a few issues
- Then...

_

Finally link-up!

Aug 29 01:35:04 arista-7050 Ebra: %LINEPROTO-5-UPDOWN: Line protocol on Interface Ethernet49 (TRANSIT: ACD), changed state to up

Aug 29 01:40:24 arista-7050 Ebra: %LINEPROTO-5-UPDOWN: Line protocol on Interface Ethernet49 (TRANSIT: ACD), changed state to down

Aug 29 01:40:28 arista-7050 Ebra: %LINEPROTO-5-UPDOWN: Line protocol on Interface Ethernet49 (TRANSIT: ACD), changed state to up

arista-7050#

Before

jared@Jareds-Desktop-iMac ~ % ping 204.42.254.15

PING 204.42.254.15 (204.42.254.15): 56 data bytes

64 bytes from 204.42.254.15: icmp_seq=0 ttl=54 time=29.590 ms

^C

--- 204.42.254.15 ping statistics ---

1 packets transmitted, 1 packets received, 0.0% packet loss

round-trip min/avg/max/stddev = 29.590/29.590/29.590/0.000 ms

After

arista-7050#ping 204.42.254.15

PING 204.42.254.15 (204.42.254.15) 72(100) bytes of data.

80 bytes from 204.42.254.15: icmp_seq=1 ttl=54 time=8.78 ms

80 bytes from 204.42.254.15: icmp_seq=2 ttl=54 time=8.69 ms

80 bytes from 204.42.254.15: icmp_seq=3 ttl=54 time=8.57 ms

80 bytes from 204.42.254.15: icmp_seq=4 ttl=54 time=8.57 ms

80 bytes from 204.42.254.15: icmp_seq=5 ttl=54 time=8.58 ms

--- 204.42.254.15 ping statistics ---


5 packets transmitted, 5 received, 0% packet loss, time 38ms

rtt min/avg/max/mdev = 8.571/8.640/8.784/0.118 ms, ipg/ewma 9.516/8.707 ms

Traceroute

```
arista-7050#traceroute 204.42.254.15
traceroute to 204.42.254.15 (204.42.254.15), 30 hops max, 60 byte packets
1 207-179-84-221.static.acd.net (207.179.84.221) 0.490 ms 1.263 ms 1.241 ms
2 gi0-1-0-subint21.router.backbone.jcsnmimn.acd.net (207.179.109.6) 2.662 ms 2.648 ms *
3 Gi4-1-0-subint21.router.backbone.lnngmimn.acd.net (207.179.109.33) 2.391 ms 2.464 ms
*
4 gi2-0-0-subint198.level3.acd.net (208.77.128.153) 2.658 ms 2.662 ms 2.640 ms
5 7-1-19.ear3.Chicago2.Level3.net (4.35.108.129) 7.675 ms 7.676 ms 7.668 ms
6 * * *
7 ae-4.r07.chcgil09.us.bb.gin.ntt.net (129.250.8.173) 8.752 ms 8.791 ms 8.859 ms
8 r204.42.254.15.nether.net (204.42.254.15) 8.589 ms 8.609 ms 8.594 ms
```

Latency reduction





Your Internet speed is

730 Mbps C

Unsolicited contact!

- IPv4 Depot
 - We noticed you stopped announcing an ARIN /24
- Cogent
 - Want transit?
 - Called me during a precious mid-day nap
 - We are ranked lower on downdetector than (insert list of competitors)
- HE
 - Want transit?

Costs?

- 2020 had the majority of them
- Major costs breakdown:
 - \$126,710
 - \$94,866 Directional boring/conduit installation
 - \$31,844 Misc materials, rentals, equipment
 - \$5,000 Surveying
 - \$856 185 CFM Air Compressor rental

Maybe still cheaper than moving? And I now have fiber!

Thank You!

- Without many people it would not be possible
- Support of many people who have been there and done that
- Ryan Peel @ VBFiber
- Chris Fabien @Lakenet
- Antawn Parks @ Millenium
- Roy Grove @ EZwisp
- My neighbors on Reese Lane, Pinecross Lane, Liberty and Parker Road
- Great Lakes Directional Boring
- Everyone who put up with me and encouraged me along the way
- ACD.Net & 123.net
- My family
- Many friends who helped with physical labor or other support

Resources

- Facebook!
 - https://www.facebook.com/groups/wisptalk/
 - https://www.facebook.com/groups/fispstuff/
 - https://www.facebook.com/groups/305841453429657/

.

FIN



Time for questions?

twitter.com/jaredmauch